EXISTING 6" C.I. CROSS (REMOVE PLUG)
INSTALL 1 - 6" C.I. NIP
1 - 6" GATE
1 - 6" x 8" INCREASER C.I.

SEE DETAIL SKETCH

YOUNG AV.

VINELAND AV.

PATTERSON AV.

SMITH AV.

ACORN STREET

8" A.C. CL 150 WATER MAIN

6" A.C. WATER MAIN

16" A.C. WATER MAIN

1" C.I. (ABANDON)

EXISTING SERVICE TO #8 SMITH & #181 PATTERSON (CLOSE AT CORP. & TIE AT EAST END 8" A.C.) ABANDON 1" C.I. & TIE IN COPPER TO EXISTING COPPER AT EAST END.

EXISTING 6"x6" CROSS

SERVICE #8 ACORN

SERVICE #181

DIRT RD.

COPPER

HYDRANT

S.M.H.

W.G.

C.B.

CONC. BD.

W.B.

M.H.

HYD. 5' OFF

POLE

13

182

98

103

181

8 ACORN

SKETCH

ACORN ST.

PATTERSON AVE.

HYDRANT

6" GATE

8"x6" REDUCER

8" GATE

6" NIP

PLUG (R.T.)

8" A.C.

8 ACORN

181 PATTERSON

3/4" C.C. TAPPED COLLARS

PLUG (R.T.)

#181

INSTALL
- 1 - 8" C.I. CROSS
- 1 - 8"x6" REDUCER
- 1 - 6" GATE
- 1 - 6" LENGTH C.I.
- 1 - HYDRANT
- 2 - 3/4" C.C. COLLARS
- 2 - LENGTHS 8" A.C. E.S.S.
- 2 - C.I. CAPS

WATER MAIN PLAN
ACORN STREET
EAST LONGMEADOW MASS.
SCALE: 1" = 40' JULY 1978
A.A. MELIEN TOWN ENG'R.

W 3659